

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Marquette COUNTY


T 45N R 30-31W

DESCRIPTION OF CORNER Section Corner 12, 13, 7, and 18

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 22, 1969

WITNESSES TO CORNER..... Maple 12 S26°W 51 lks. "S13 NBT"



Maple 11 N50°W 19½ lks. "S12 NBT"

Balsam 6 S40°E 7 lks. "S18 NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed at site of a squared wood post scribed with the section numbers, set by unknown party on unknown date, and apparently used as the corner for many years. Found no evidence of the original corner monument or its accessories. Distances to natural features mentioned in the original field notes between this post and the township corner to north show good agreement in general (one notable exception at N 1/16 corner between Sec. 7 and 12), but to south are indefinite. The undersigned believes that a corner position 50 to 70 links west of the found post more nearly matches field note calls, but positive proof being difficult, this corner was perpetuated as it stands.

Variation at this corner is about 3°45' West.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 10/20/69  
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing