

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Marquette COUNTY


T 45N R 30-31W

DESCRIPTION OF CORNER 1/4 corner between Sections 7 and 12

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 30, 1969

WITNESSES TO CORNER..... Tamarack 8 S32 $\frac{1}{2}$ <sup>o</sup>W 29 lks. "1/4S NBT"



B. Spruce 7 N58 $\frac{1}{2}$ <sup>o</sup>W 14 $\frac{1}{2}$  lks. "1/4S NBT"

Tamarack 12 N74 $\frac{1}{2}$ <sup>o</sup>E 29 lks. "1/4S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by proportionate measurement on line between Sec. Corner 40.035 chains South and Township Corner 121.958 chains North. Found no evidence of original corner or its accessories or of any replacement monument or its accessories. Corner is 4.86 chains north of a swamp edge mentioned in original field notes as being 5.00 chains south of corner and 0.25 chain south of the bottom of a ridge mentioned as being 0.50 chain north of corner.

Variation at this corner is about 2<sup>o</sup>15' West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Arthur O. Enger DATE 10/20/69  
REGISTERED LAND SURVEYOR

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68