

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Marquette COUNTY


T 45N R 30-31W

DESCRIPTION OF CORNER Section Corner 13, 18, 19, and 24

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 28, 1969

WITNESSES TO CORNER..... Red Maple 8 S61°E 23 lks. "S19 NBT"



Balsam 9 N4½°E 26 lks. "S18 NBT"

W. Birch 9 S68°W 22 lks. "S24 NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed at a position which corresponds with original field note calls to ridge tops to east, west, north, and south of corner. General location of corner established from measurements on transit line on east side of T45N, R31W. The ridge tops to north, south, and west are high and narrow with only a small error possible in picking the top. The ridge to east is a little less definite, but there is good agreement with the record call to ascend the hill. Found no evidence of original corner or accessories. Found a 15" aspen that has been marked with paint for an approximate corner bearing N61°E 68 links from monument placed here.

Note: Found distance across Little Sundog Lake on Section Line between 19 and 24 to be 21.04 chains (by triangulation). Record distance is 23.33 chains. Evidently a mistake was made in the original government survey triangulation, as the lake level has been artificially raised since the original survey and even now is less wide than reported at that time. The corner as re-established here lies 2.655 chains north of the north edge of the present lake, but was reported as 3.36 chains originally. The difference of .705 chains can be at least partially accounted for by the present higher lake level, but tends to confirm the position of the corner as re-established here.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

10/21/69

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68