

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron-Marquette COUNTY
T 45N R 30-31W

DESCRIPTION OF CORNER South 1/16 corner between Sections 19 and 24

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 29, 1969

WITNESSES TO CORNER..... Red Maple N61°W 45 lks. "1/16 S BT"



White Birch S13°E 52 lks. "1/16 S BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument set on line between section corner 20.00 chains south and 1/4 corner 20.00 chains north. Found no evidence of a corner ever having been established here or in the vicinity.

Variation at this corner is about 3° West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

10/21/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68