

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Marquette COUNTY


T 45N R 30-31W

DESCRIPTION OF CORNER 1/4 corner between Sections 19 and 24

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 29, 1969

WITNESSES TO CORNER..... B. Spruce 4 S5 $\frac{1}{2}$ ^oW 8 $\frac{1}{2}$ lks. "1/4 S NBT"



B. Spruce 5 N57^oW 31 lks. "1/4 S NBT"

Balm of Gilead 12 N41^oE 14 $\frac{1}{2}$ lks. "1/4 S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed on line between section corner 40.00 chains south and section corner 38.66 chains north. Measurements across Little Sundog Lake on the north half mile of this section line indicate the probability of a mistake in triangulation across the lake at the time of the original survey, accounting for the large difference in the chainage between the south half mile and the north half mile. Present distance across lake on this line is 21.04 chains as against 23.33 chains record distance. As the level of the lake is now artificially raised above its original level, the distance across it was probably even shorter at the time of the original survey than it is now. This condition was taken into account in re-establishing the NE corner of Sec. 24, which was set by measurements from ridge tops and the N. edge of the lake.

This 1/4 corner was placed at the record 40.00 chains from the SE corner of Sec. 24 as it seems to best fit the evidence on the ground. It lies 71 links north of a low ridge mentioned as being 1.00 chain south of the corner originally.

No evidence of original corner or accessories.

SURVEYOR'S SEAL

SIGNED Arthur C. Enger DATE 10/21/69
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68