

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD

Iron-Marquette COUNTY


T 45N R 30-31W

DESCRIPTION OF CORNER 1/4 corner between Sections 13 and 18

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 29, 1969

WITNESSES TO CORNER..... Basswood N41 $\frac{1}{2}$ ^oW 17 lks. "1/4 S NBT"



Sugar Maple N54 $\frac{1}{2}$ ^oE 15 lks. "1/4 S NBT"

Ironwood S8^oW 42 lks. "1/4 S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed on line between section corner 40.00 chains south and section corner 42.61 chains north. The unequal distances are occasioned by the belief (from calls to natural features in the original field notes) that an error was made in the original survey of this section line. As it was considered impossible to exactly de-limit the place where the error might have occurred, it was thought satisfactory to make the south half-mile equal to the record distance and put the excess distance all into the north half-mile. The corner as re-established lies about 8.33 chains north of a prominent ridge mentioned in the original notes as being 9.00 chains south of the 1/4 corner. This location falls in an area which has trees of the same species as the original BT's. No evidence of the original corner monument or its accessories was found.

Variation at this corner is about 1^o30' West.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

10/21/69

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68