


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 45N R 31-32W

DESCRIPTION OF CORNER 1/4 corner between Sections 31 and 36
CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED August 19, 1969
WITNESSES TO CORNER..... W. Pine 13 N30°W 23½ links "1/4S, NBT"



W. Pine 14 N75°E 28 links "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed on line between an original section corner $N0^{\circ}10' 55''E$ 40.078 chains and a re-established township corner $S0^{\circ}10' 55''W$ 40.078 chains. (Bearing computed from solar observation). Found no evidence of original corner post or its accessories. Found a L. E. S. post marked "APP" $S67^{\circ}E$ 69½ links from corner, with a Northern Paper Mills L. P. bearing date 6/30/43 and names E. A. Wilson and R. S. Peterson and notation "Approximate 1/4 S" on a nearby tree.

Variation at this corner is $0^{\circ}45'$ West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur C. Enger
REGISTERED LAND SURVEYOR

DATE

1/28/71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68