

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 45N R 31-32W

DESCRIPTION OF CORNER South 1/16 corner between Sections 25 and 30

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 23, 1969

WITNESSES TO CORNER..... Sugar Maple 16 N3°E 52½ lks. "1/16S, BT"



Sugar Maple 6 S60°W 12 lks. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed on line between an original section corner 20.057 chains south and an original 1/4 corner 100.287 chains north. Found no evidence that the corner had been established previously.

Variation at this corner is 1°40' West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

1/28/71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68