


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 45N R 31-32W

DESCRIPTION OF CORNER North 1/16 corner between Sections 25 and 30
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED May 6, 1969
WITNESSES TO CORNER..... Red Maple 8 S17°W (Mag) 42½ lks. "1/16S, BT"



Red Maple 10 N10°W (Mag) 16 lks. "1/16S, BT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by proportionate measurement on line between an original section corner 60.172 chains south and an original 1/4 corner 60.172 chains north. Found no evidence that the corner had been previously established.

Variation at this corner is 2°55' West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

11/28/71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68