


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron - Marquette COUNTY

T 45N R 30-31W

DESCRIPTION OF CORNER Section Corner 25, 30, 31 and 36
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED October 4, 1968
WITNESSES TO CORNER..... Wh. Spruce 4 S35°W 14 lks. "S36 NBT"



Wh. Spruce 8 S62°E 56 lks. "S31 NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by proportionate measurement on line between a 1/4 corner 39.953 chains North and the township corner 79.907 chains South. Found no evidence of the original corner or its accessories, but did find a 3/4" iron reinforcing rod N69°W 1.037 chains from the corner set here. Reinforcing rod set by unknown surveyor and there is a Ford Motor Co. location poster nearby. From the rod to the south shore of Fence Lake measures 5.60 chains, as compared to the record measure of 5.45 chains. From the corner set here the measurement to the lake shore is about 5.40 chains, depending on where the water's edge is taken to be. It is felt that the lake measurements are inconclusive as to corner location in themselves, but that over all measurements support the corner re-established here over the found reinforcing rod.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur P. Enger
REGISTERED LAND SURVEYOR

DATE

1/22/71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68