


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES  
LAND CORNER RECORD

Iron COUNTY  
T 45 N R 31 W

DESCRIPTION OF CORNER Section Corner 16, 17, 20, and 21  
CORNER MONUMENT 1" I.D. iron pipe with 4" aluminum cap.  
DATE MONUMENT PLACED AND WITNESSED September 30, 1970  
WITNESSES TO CORNER..... Corner lies in leatherleaf bog on wet grassy margin of



a small stream. No nearby trees for witnesses.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established basically by measuring a transit line from an original corner 2 miles north, then establishing corner position by record distances to stream crossings 8.82 ch. N, 5.60 ch. S, and 0.25 ch. W of corner. Position fits as nearly as can be determined with original field note calls on section lines N & S of corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE August 30, 1971

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68