


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 45 N R 31 W

DESCRIPTION OF CORNER East 1/16 corner between Sections 4 and 9
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.
DATE MONUMENT PLACED AND WITNESSED July 29, 1971
WITNESSES TO CORNER..... Red Maple 5 (NW'ly of twins) N51 $\frac{1}{2}$ °E (mag.) 32.7 ft. "1/16S,NBT"



Red Maple 5 S76°E (mag.) 35.9 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No evidence that the corner had been previously established.

Corner established on line between section corner 19.917 ch. east
and 1/4 corner 19.917 ch. west.

Variation about 2°30' East.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

August 30, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68