


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 45 N R 31 W

DESCRIPTION OF CORNER Section Corner 8, 9, 16, and 17
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.
DATE MONUMENT PLACED AND WITNESSED November 13, 1970
WITNESSES TO CORNER..... Aspen 8 N27^oW (magnetic) 28.5 ft. "S8, NBT"



Aspen 8 S 2^oE (magnetic) 4.2 ft. "S16, NBT"
Maple 6 N61^oE (magnetic) 33.1 ft. "S 9, NBT"
AND
Spruce 4 S41^oE (magnetic) 43.7 ft. "S16, NBT"

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established basically by measuring transit lines from original corners 1 mile east and 1 mile north, then establishing the corner position by orientation with natural features called for in original field notes. A position 79.84 ch. west of the corner to east and 80.26 ch. south of the corner to north agrees well with the original field notes.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE August 27, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68