## STATE OF MICHIGAN DEPARTMENT 0F NATURAL RESOURCES

## LAND CORNER RECORD

				Iron	COUNTY
				T 45 N	R <u>31 W</u>
DESCRIPTION OF CORNER	1/4 corner be	tween S	ections 2 ar	nd 3	·
CORNER MONUMENT1" 1	.D. x 36" iron	pipe w	ith 4" alum	Inum cap	
DATE MONUMENT PLACED AND	WITNESSED _	Novemb	er 30, 1970	<del></del>	······
VITNESSES TO CORNER	. W. Pine 20	S10°E	(magnetic)	33.7 ft.	"1/4S, NBT"
N	W.Spruce	N35°E	(magnetic)	30.9 ft.	"1/4S, NBT"
\$ <b>2</b>					
	AND				
CIRCLE CORNER REGISTER	RED				

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed proportionately on line between section corner 40.083 ch. south and section corner 40.975 ch. north.

Variation is about 14°15' West.

SURVEYOR'S SEAL

SIGNED

REGISTERED LAND SURVEYOR

DISTRIBUTION:

Arthur O. Enger

County Courthouse Area Forester (Regions I & II) District or Region Surveyor Forestry Div., Lansing

R 4047 Rev. 10/68