

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Marquette COUNTY


T 45 N R 30-31 W

DESCRIPTION OF CORNER Section Corner 19, 24, 25, and 30

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED April 15, 1969

WITNESSES TO CORNER..... B. Spruce 7 S27°E (magnetic) 68½ links "S30, NBT"



B. Spruce 7 S23°W (magnetic) 99 links "S25, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No replacement monument found. Nearby county boundary signs indicate proximity of N & S township line.

Found fence line running south on south side of county road to establish departure of corner. Notes of a 1933 survey on file in the Marquette County Road Commission office report finding a wood post 2 feet south of an E & W fence line on north side of county road. Found no trace of this post, so set corner 2 feet south of fence, which appears to pre-date 1933. Found this position to be N0°21'E 39.995 ch. of 1/4 post between Section 25 & 30 in fence line south. Position checks reasonably well with call to lake edge and stream to south.

Near side of vertical post of rustic sign marked "Marquette-Iron County" is S86°E 20½ links.

Corner in ditch on north side of E & W county road.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

August 27, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68