


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 45 N R 31-32 W

DESCRIPTION OF CORNER 1/4 corner between Sections 25 and 30
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED May 23, 1969
WITNESSES TO CORNER..... Balsam 8 N14°W (magnetic) 51½ links "1/4S, NBT"



Sugar Maple 8 S29°E (magnetic) 22 links "1/4S, NBT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found no replacement monument(s). Found dead and down cedar cruiser's tree N80°W 23 links from corner.

Corner re-established by proportionate measurement on line between original section corner 40.115 ch. south and original 1/4 corner 80.229 ch. north. Found rotted sugar maple stump N19°W 26 links, possibly an original BT, but no marks.

Variation about 3°00' West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE August 27, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68