

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 45 N R 31-32 W

DESCRIPTION OF CORNER Section Corner 19, 24, 25, and 30

CORNER MONUMENT 1" I.D. iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED May 6, 1969

WITNESSES TO CORNER..... W. Spruce 13 N76°E (magnetic) 51 links "S19, NBT"



Red Maple 10 N14°W (magnetic) 51½ links "S24, NBT"

Red Maple 5 S24°W (magnetic) 57½ links "S25, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found point of rotted post in ground N44°W 21 links with Northern Paper Mills tag on nearby dead aspen tree. Tag says "about Sec. Cor. B.G.B., 1942," indicating an approximate corner.

Corner placed on line between an original section corner 80.229 chains south and an original 1/4 corner 40.115 chains north.

Variation about 0°45' West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE August 27, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68