


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY  
T 45 N R31-32 W

DESCRIPTION OF CORNER South 1/16 corner between Sections 19 and 24  
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.  
DATE MONUMENT PLACED AND WITNESSED May 6, 1969  
WITNESSES TO CORNER..... W. Spruce 9 S51°E (magnetic) 39 links "1/16S, BT"



Red Maple 6 S67°W (magnetic) 25 links "1/16S, BT"  
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No evidence of previous establishment. Established on line  
between section corner 20.058 ch. south and 1/4 corner 20.058 ch. north.

Variation about 2°10' West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE August 24, 1971

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68