


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY  
T 45 N R 31-32 W

DESCRIPTION OF CORNER Section Corner 13, 18, 19, and 24  
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap  
DATE MONUMENT PLACED AND WITNESSED March 16, 1970  
WITNESSES TO CORNER..... Cedar 8 N10°E (magnetic) 11.1 feet "S18, NBT"



Cedar 12 S72°W (magnetic) 61.8 feet "S24, NBT"  
Hemlock 20 N22°W (magnetic) 46.5 feet "S13, NBT"  
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found intersecting old N-S and E-W blazed lines at corner.

Monument placed on line between original section corner 160.064 ch. north and original 1/4 corner 40.016 ch. south, because no positive original evidence could be confirmed. Found an 8" dead cedar cruiser's tree S78°E 7.2 feet from corner with legible names dating from 1914. Also found a 15" cedar to NW with a very old blaze facing corner.

Variation about 2°00' West.

SURVEYOR'S SEAL

SIGNED

*Arthur P. Enger*  
REGISTERED LAND SURVEYOR

DATE

August 23, 1971

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68