


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T T45N R 31-32W

DESCRIPTION OF CORNER 1/4 corner between Sections 7 and 12
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED March 17, 1970
WITNESSES TO CORNER..... Cedar 19 S17°E (magnetic) 45.5 feet "1/4S, NBT"



Balsam 7 N33°E (magnetic) 4.4 feet "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 19" cedar with old blazes on four sides bearing S17°E 69 links from corner, for approximate corner.

Monument placed on line between section corners 40.016 ch. to N & S. Found no evidence of original monument or accessories. Approximate corner tree is 77 links north of north bank of Fence River, original field notes placed corner 1.30 ch. north of river. Corner as established is 1.35 ch. north of river. Found no trace of meander corners on river bank.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

August 24, 1971

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68