

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY  
T 45 N R 31W

DESCRIPTION OF CORNER 1/4 corner between Sections 15 and 16

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED October 30, 1969

WITNESSES TO CORNER..... (Forked) Tamarack 7 S67°E (magnetic) 22½ links "1/4S, NBT"



Tamarack 4 S9½°W (magnetic) 43½ links "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Placed monument at site of four very old squared wood posts or points of posts. One or more probably pre-date this century, and possibly one is the point of the original post, preserved in the wet swamp bottom. Position checks well with a small lake recorded as being 1.50 ch. east of corner and with original section corner one-half mile north.

SURVEYOR'S SEAL

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE

August 24, 1971

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68