

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 45N R 31-32W

DESCRIPTION OF CORNER Section Corner 7, 12, 13, and 18

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED March 13, 1970

WITNESSES TO CORNER..... Sugar Maple 10 S51°E (mag.) 11.1 feet "S18, NBT"



Sugar Maple 7 S24°W (mag.) 23.9 feet "S13, NBT"

Sugar Maple 9 N40°W (mag.) 13.7 feet "S12, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a squared post set by Land Economic Survey in 1930's S30°E 41 links;
marked approximate corner.

Monument placed by proportionate measurement on line between original section
corner 80.032 ch. north and original 1/4 corner 120.048 ch. south.

Variation about 2°00' west.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE August 20, 1971
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68