

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 45 N R 31-32 W

DESCRIPTION OF CORNER 1/4 corner between Sections 13 and 18

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED March 16, 1970

WITNESSES TO CORNER..... Sugar Maple 8 N15^oW (mag.) 19.1 feet "1/4S, NBT"



Sugar Maple 9 S26^oW (mag.) 18.7 feet "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found location tag on 8" maple N55^oW 33.5 feet indicating approximate corner area.

Monument placed on line between section corners 40.016 ch. to north and south.

Also placed MDNR location tag on 4" maple on south edge of woods road about 7.67 ch. north of corner.

Variation about 2^o00' west.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur P. Enger
REGISTERED LAND SURVEYOR

DATE

August 20, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68