

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY  
T 45 N R 31 W

DESCRIPTION OF CORNER 1/4 corner between Sections 3 and 4

CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED September 11, 1970

WITNESSES TO CORNER..... W. Spruce 10 S 4°E (magnetic) 13.3 ft. "1/4S, NBT"



W. Spruce 10 N74°E (magnetic) 12.1 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by proportionate measurement on line between section corner 39.975 ch. south and section corner 40.485 ch. north. Also squared and scribed a 4" red maple 4 links west of iron pipe. Erratic N & S single-wire fence line is .53 ch. west.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR

DATE July 21, 1971

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68