

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 45 N R 31 W

DESCRIPTION OF CORNER Section Corner 3, 4, 9, and 10

CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 4, 1970

WITNESSES TO CORNER..... B. Spruce 10 N 9°E (magnetic) 17.0 ft. "S 3, NBT"



B. Spruce 12 S64°E (magnetic) 26.2 ft. "S10, NBT"

B. Spruce 10 S40°W (magnetic) 65.4 ft. "S 9, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found recent spruce post at single-wire fence intersection 2.00 ch. S and 1.60 ch. W of corner, used for approximate corner. No evidence to support it.

Monument placed by double proportionate measurement from corners 1 mile N, 1½ miles S, 3 miles E, and 1 mile W. Distances to several natural features north and south of the established position correspond well with description in original field notes. Corner falls on side hill trending NE as called for in original record.

SURVEYOR'S SEAL

SIGNED Arthur P. Eger DATE July 27, 1971
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68