

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY  
T 45 N R 31 W

DESCRIPTION OF CORNER 1/4 corner between Sections 3 and 10

CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED August 17, 1970

WITNESSES TO CORNER..... Balsam 4 S13°W (magnetic) 9.6 ft. "1/4S, NBT"



Aspen 8 N70°W (magnetic) 26.5 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed on line between section corners 40.084 ch. to east and west.  
E & W single-wire fence line is about 1 1/2 ch. south of corner, but is erratic in  
direction and has nothing to support it as being on the section line.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE July 26, 1971  
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68