

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. <u>X</u> R. <u>31</u> W.	K-9
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 8, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner K-9: Original monument and accessories not found. Found a 1" x 1" square x 20" long iron pin lying horizontal about 4" beneath county road surface, with pointed end toward NW and mushroomed top end toward SE. Probably bent over by grader. Pin appears very old.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner K-9: Reestablished, by assuming pointed end of iron pin to have been at or near the point where initially put in ground, by driving pin vertically into ground at that point a distance of approximately 6" below surface of county road. Corner is in line with old fence going north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
**Corner K-9: 1" x 1" square x 20" long iron pin.
 7" Aspen S35°E 38.13 ft., NBT (nail with brass D.N.R. reference tag)
 8" Tamarack S52°W 45.10 ft., NBT (nail with brass D.N.R. reference tag)
 Power Pole N79°W 85.56 ft., (nail with brass D.N.R. reference tag)**

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson DATE 7/22/80
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY Keith L. Sackett DATE 10-13-80
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

