

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. R. 31 <input checked="" type="checkbox"/> W.	I-6
2. PROPERTY CONTROLLING IN SECTION-15	T. 45 N. R. 31 <input checked="" type="checkbox"/> W.	14
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. S. W.	
4. LOT NO. RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 20, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and, or subsequent restoration:

Corner I-6: Original monument and accessories not found.

Corner 14: Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and, or method applied in restoring or re-establishing corner:

Corner I-6: Restored on line between section corners north and south.

Corner 14: Established on line between section corner south and 1/4 corner north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner I-6: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
Spruce S37°E 38.4 ft., 1/4S, NBT
W. Birch N68°E 45.2 ft., 1/4S, NBT

Corner 14: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
6" Spruce S47°W 18.1 ft., 1/16S, BT
3" Spruce N 5°E 22.7 ft., 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-27-81
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

