

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

	(IRON COUNTY)	CORNER CODE NUMBER
FOR CORNERS OF--	LOCATED IN--	
1. PUBLIC LAND SURVEY	T. 45 N. R. 31 W. <input checked="" type="checkbox"/>	M.C. Bet. K-7 & K-8
2. PROPERTY CONTROLLING IN SECTION 10	T. 45 N. R. 31 W. <input checked="" type="checkbox"/>	7
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. <input type="checkbox"/>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner 7: Not set on original survey nor subsequently, apparently.**
- Corner M.C. Between K-7 & K-8: Original monument and accessories not found.**

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner 7: Established 08-20-80 on line between corners north and south.**
- Corner M.C. Between K-7 & K-8: Restored 08-27-80 between corners north and south 35 feet north of original placing. Corner falls in stream inlet from north.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner 7: Set 1" I.D. x 36" I.P. with 4" aluminum cap.**
 4" W. Birch S 50°E 32.8 ft., 1/16S, BT
 7" Spruce N15°W 84.4 ft., 1/16S, BT
- Corner M.C. Between K-7 & K-8: Set 4" Sq. Cedar Post in water 4 ft. deep.**
 7" Tamarack S34°W 27.7 ft., MC, NBT
 7" Tamarack N58°E 28.6 ft., MC, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-27-81
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006