

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. 31 W. <input checked="" type="checkbox"/> R. <input type="checkbox"/>	K-2, H-5
2. PROPERTY CONTROLLING IN SECTION	T. 45 N. 31 W. <input checked="" type="checkbox"/> R. <input type="checkbox"/>	3
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W. <input type="checkbox"/>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner K-2: Original monument and accessories ~~not~~ found.
  - Corner 3: Not set on original survey nor subsequently, apparently.
  - Corner H-5: Original monument and accessories not found.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner K-2: Restored 08-11-80 proportionately between section corner 40.000 chains south and section corner 41.270 chains north.
  - Corner 3: Established 08-12-80 on line between section corner 20.000 chains north and north M.C. 2.860 chains south.
  - Corner H-5: Restored 08-12-80 on line between section corners 40.078 chains to east and west.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner K-2: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
    - 7" Tamarack S21°E 15.3 ft., 1/4S, NBT
    - 7" Tamarack N38°W 11.6 ft., 1/4S, NBT
    - 16" W. Pine S51°W 28.4 ft., 1/4S, NBT
  - Corner 3: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
    - 4" Tamarack N28°E 22.1 ft., 1/16S, BT
    - 4" Tamarack S11°W 35.8 ft., 1/16S, BT
  - Corner H-5: Set 1" I.D. x 32" iron pipe with 4" aluminum cap.
    - 16" Spruce N86°W 5.5 ft., 1/4S, NBT
    - 12" Spruce S14°W 21.7 ft., 1/4S, NBT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-27-81  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006