

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. <input checked="" type="checkbox"/> R. 31 <input checked="" type="checkbox"/> W.	I-4
2. PROPERTY CONTROLLING IN SECTION 10	T. 45 N. <input checked="" type="checkbox"/> R. 31 <input checked="" type="checkbox"/> W.	15, 16
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner 15: Not set on original survey nor subsequently, apparently.
- Corner 16: Not set on original survey nor subsequently, apparently.
- Corner I-4: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner 15: Established 08-13-80 on line between Sec. Cor. 20.039 chains west and 1/4 cor. 20.039 east.
- Corner 16: Established 08-14-80 on line between Sec. Cor. 20.039 chains east and 1/4 corner 20.039 chains west.
- Corner I-4: Restored 08-14-80 on line between Sec. Corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner 15: Set 1" I.D. x 32" iron pipe with 4" aluminum cap.
Maple N19°E 7.1 ft., 1/16S, BT
Maple S36°W 20.7 ft., 1/16S, BT
- Corner 16: Set 1" I.D. x 32" iron pipe with 4" aluminum cap.
5" Spruce N61°W 7.1 ft., 1/16S, BT
5" Spruce S68°E 26.7 ft., 1/16S, BT
- Corner I-4: Set 1" I.D. x 32" iron pipe with 4" aluminum cap.
9" Spruce N79°W 18.4 ft., 1/4S, NBT
9" Cherry S22°E 27.3 ft., 1/4S, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-27-81
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett (SEAL)

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006