

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 45 N. X, R. 31 X. W.	L-3
2. PROPERTY CONTROLLING IN SECTION 12.....	T. 45 N. X, R. 31 X. W.	2, 1
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S, R. E. W.	
4. LOT NO. ...., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 11, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner L-3: Original monument and accessories not found.
- Corner 2: Not set on original survey nor subsequently, apparently.
- Corner 1: Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner L-3: Restored on line between section corners 39.976 chains east and west.
- Corner 2: Established on line between section corner 19.988 chains east and 1/4 corner 19.988 chains west.
- Corner 1: Established on line between sec. corner 19.988 chains west and 1/4 corner 19.988 chains east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner L-3: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.  
12" Tamarack S 4°W 27.2 ft., 1/4S, NBT  
9" Tamarack N53°E 37.8 ft., 1/4S, NBT
- Corner 2: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.  
4" Maple N 4°W 8.1 ft., 1/16S, BT  
5" Maple S51°W 17.6 ft., 1/16S, BT
- Corner 1: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.  
9" Spruce S26°E 22.2 ft., 1/16S, BT  
4" Spruce N26°W 44.3 ft., 1/16S, BT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-27-81

CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006