

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located In:	Corner Code #1
(County)		
1 Public Land Survey	T 45N R 31W	K10
	T R	K11
	T R	K12
2 Property Controlling in Section	S 25 T R	10
	S T R	
3 Miscellaneous Property in Sec.	S T R	

Register of Deeds Stamp & File Number

4 Lot No _____, Recorded Plat _____
 5 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	14	15	16	17	18							
7													
8	19	20	21	22	23	24							
9													
10	25	26	27	28	29	30							
11													
12	31	32	33	34	35	36							
13													

I, Keith Sackett, in a field survey on June 15, 1988, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K10	K11	10	K12
Original monument and accessories not found.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K10	K11	10	K12
Restored midway on line.	Restored by double proportion.	Established midway on line.	Restored midway on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

K10	K11	10	K12
Set 1"x32" I.P. w/4" aluminum cap.	Set 1"x36" I.P. w/4" aluminum cap.	Set 1"x 36" I.P. w/4" aluminum cap.	Set 1"x36" IP w/4" aluminum cap.
4" balsam N86E 39.0' 1/4s NBT	10" maple N84E 32.8' S25 NBT	5" spruce S46E 17.9' 1/1As BT	2 1/2" red pine S45W 18.4' 1/4s NBT
4" spruce S37W 5.5' 1/4s NBT	5" hophorn beam S07W 37.0' S35 NBT	10" spruce S52W 33.5' 1/16s BT	6" spruce N14W 25.0' 1/4s NBT
6" spruce N20W 9.5' 1/4s NBT	5" maple N15W 38.6' S26 NBT	14" aspen N33W 4.1' 1/16s BT	12" red pine N45E 17.8' 1/4s NBT

Signed by Keith Sackett Date 12-9-88

Surveyor's Michigan License No. 19006