

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located in:	Corner Code -##
(County)		
1 Public Land Survey	T 45N R 31W	111
	T R	
	T R	
	T R	
2 Property Controlling in Section	S 36 T R	1
	S T R	2
3 Miscellaneous Property in Sec	S 25 T R	3
	S T R	

Register of Deeds Stamp & File Number

4 Lot No. , Recorded Plat _____
 5 Private Claims _____

I, Keith Sackett in a field survey on June 15, 1988, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A Description of original monument and accessories and/or subsequent restoration:

111	1	2	3
Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

111	1	2	3
Restored midway on line.	Established midway on line.	Established midway on line.	Established midway on line.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:

111	1	2	3
Set 1" x 32" I.P. w/4" aluminum cap.	Set 1" x 36" I.P. w/4" aluminum cap.	Set 1" x 36" I.P. w/4" aluminum cap.	Set 1" I.D. x 36" I.P. w/4" aluminum cap.
7" spruce N11W 13.0' 1/4s NBT	4" spruce S27E 14.3' 1/16s BT	14" balsam S66W 42.0' 1/16s NBT	6" tamarack N32W 11.5' 1/16s BT
4" tamarack S62E 3.9' 1/4s NBT	6" spruce N06E 12.5' 1/16s NBT		
7" spruce S79W 21.5' 1/4s NBT	8" spruce S59W 20.5' 1/16s BT	7" sugar N80W 43.3' 1/16s NBT	10" spruce S66W 14.1' 1/16s BT
		9" sugar N54E 77.1' 1/16s NBT	11" spruce S05E 20.6' 1/16s BT

Signed by Keith Sackett
 Surveyor's Michigan License No. _____ 1900s _____

Date 12-9-88