

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Iron

(County)	Located In:	Corner Code #
1 Public Land Survey	T 45N R 31W	112
	T R	
	T R	
	T R	
2 Property Controlling in Section	S 35 T R	2
	S T R	10
3 Miscellaneous	S T R	
Property in Sec	S T R	

Register of Deeds Stamp & File Number

4 Lot No \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5 Private Claims \_\_\_\_\_

I, Keith Sackett, in a field survey on June 22, 1988, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
6													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration.

112	2	10
Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

112	2	10
Restored midway on line.	Established midway on line.	Established midway on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

112	2	10
Set 1"x36" I.P. w/4" aluminum cap.	Set 1"x36" I.P. w/4" aluminum cap.	Set 1"x32" I.P. w/4" aluminum cap.
4" spruce N74W 44.0' 1/4S NBT	10" spruce N86W 11.1' 1/16S BT	3" maple S01E 5.2' 1/16S BT
2" spruce S30E 27.0' 1/4S NBT	8" spruce East 24.8' 1/16S BT	2" spruce S46E 35.0' 1/16S BT
3" spruce East 24.5' 1/4S NBT	7" spruce S40E 34.9' 1/16S BT	24" red pine stump .7' 1/16S BT
	squared spruce N45W .5'	2" sq. post nailed to red pine stump marked 1/16S BT, painted blue.

Signed by Keith Sackett Date 12-22-88

Surveyor's Michigan License No 19006