

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Iron

(County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 31W	C1
	T 45N R 31W	B1
	T R	
	T R	
2. Property Controlling In Section	S 6 T 45N R 31W	7
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Stephan J. Szyszkoski, in a field survey on April 27, 1993, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C1) Section corner common to Sections 5-6, T45N-R31W, and Sections 31-32 T46N-R31W. Original corner established 1846 by U.S. Deputy Surveyor John Burt. Original BTs: Fir 14 N41E 23, Cedar 18 N71/2W 31, Y. Birch 12 S17E 29, Y. Birch 10 S62W 55. In 1935, B.G. Buell of Patten Timber Co. (now Med Lake Land and Timber Co.) notes "Set cedar post" and that Cedar OBT was recovered "Down, I.N. plain". Found no subsequent record.

(B1) 1/4 corner common to Section 6 T45N-R31W, and Section 31 T46N-R31W. Original corner established in 1846 by U.S. Deputy Surveyor John Burt. Original BTs: Sugar 8 N11E 27, Spruce 10 N27W 26. In 1935, B.G. Buell of Patten Timber Co. (now Med Lake Timber and Land Co.) notes "no trace" of the OBTs. Found no subsequent record.

(7-Sec. 6) North 1/16 corner between Sections 5-6. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C1) Recovered remains of old cedar post, down, at record bearing and distance from remains of original cedar bearing tree (down and in very poor condition, no iron marks visible), and at record bearing and distance from probable stump hole of the original fir BT. Original Y. Birch BT to SE not recovered, Y. Birch to SW would have been destroyed by an old skid trail. A Colotex location poster signed by a number of individuals, on an old 25" blazed cherry, faces the corner. At the position of the downed post, I placed a 1"x36" iron pipe, capped with a 4" dia. cast aluminum MDMR tablet, appropriately stamped.

(B1) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner. Reestablished the corner on a straight line between section corner 2638.81' east and township corner 2655.30' west, being 40 chains, proportionate measure, west of the section corner. At the position for the corner, placed a 1"x36" iron pipe capped with a 4" dia. cast aluminum MDMR tablet, appropriately stamped. From the corner monumented, found a 3/4" iron pipe, placed by unknown persons, N40W 18.9'.

(7-Sec. 6) Established the corner on a straight line between quarter corner 1321.02' south and section corner 1304.49' north, being the proportionate position. At the position for the corner, I placed a 1"x36" iron pipe capped with a 4" dia. cast aluminum MDMR tablet, appropriately stamped. From the corner monumented, an iron fence post, set in a rock mound, bears N72E 16.1'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C1) Set a 1"x36" pipe with 4" cap.  
 Blazed and scribed the following new bearing trees (bearings magnetic):  
 25" Cherry N12E 4.9" "S32 NBT"  
 12" Maple N77W 29.7" "S31 NBT"  
 5" Maple S18W 16.4" "S6 NBT"  
 5" Sugar S52E 11.7" "S5 NBT"  
 Set a squared post 1 ft. north.

(B1) Set 1" pipe with 4" cap.  
 Blazed and scribed the following new bearing trees (bearings magnetic):  
 5" spruce S34E 3.2" "1/4S NBT"  
 4" maple S65W 20.4" "1/4S NBT"  
 6" spruce N56E 4.7" "1/4S NBT"  
 12" spruce N23W 4.6" "1/4S NBT"

(7-Sec. 6) Set 1" pipe with 4" cap.  
 Blazed and scribed the following bearing trees (bearings magnetic):  
 15" Sugar S56W 13.2" "1/16S BT"  
 12" Sugar N52E 11.3" "1/16S BT"  
 8" Sugar S02W 15.4" "1/16S BT"  
 10" Sugar N05W 28.7" "1/16S BT"

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	14	15	16	17	18	19	20	21	22	23	24	25	26
4	27	28	29	30	31	32	33	34	35	36	37	38	39
5	40	41	42	43	44	45	46	47	48	49	50	51	52
6	53	54	55	56	57	58	59	60	61	62	63	64	65
7	66	67	68	69	70	71	72	73	74	75	76	77	78
8	79	80	81	82	83	84	85	86	87	88	89	90	91
9	92	93	94	95	96	97	98	99	100	101	102	103	104
10	105	106	107	108	109	110	111	112	113	114	115	116	117
11	118	119	120	121	122	123	124	125	126	127	128	129	130
12	131	132	133	134	135	136	137	138	139	140	141	142	143
13	144	145	146	147	148	149	150	151	152	153	154	155	156

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6-28-93

