

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located In:	Corner Code ##
(County)		
1. Public Land Survey	T 45N R 31W	A2
	T 45N R 31W	A3
	T R	
	T R	
2. Property Controlling in Section	S 6 T 45N R 31W	10
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on April 27, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

(A2) Quarter corner common to Section 6 T45N-R31W and Section 1 T45N-R32W. Original corner established in 1846 by U. S. Deputy Surveyor John Burt. Original OTs: Sugar 6 S76N 25, Sugar 12 N61E 9. In 1935, O.G. Buell of Patten Timber Co. (now Med Lake Timber and Land Co.) notes "no trace" of OTs. Found no subsequent record.

(A3) Corner common to Sections 6-7 T45N-R31W, and Sections 1-12 T45N-R32W. Corner previously recorded by Arthur O. Enger, RLS, in 1971 as a 1" I.D. pipe with 2" brass Northern Paper Mills cap set from an original OT. 1971 bearing trees: Sugar Maple 9 N72E 39.8', Sugar Maple 8 S8 1/2E 29.3'. Found no subsequent record.

(10-Sec. 6) South 1/16 corner between Section 6 T45N-R31W and Section 1 T45N-R32W. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A2) Original post and accessories not recovered. There are several very old Sugars in corner area, but could not make anything fit reasonably with record of original OTs or line measurements north and south. Felled a 24" Sugar, being a suspected OT, but found no evidence of markings, it being quite hollow. Reestablished the corner on a straight line between Section corner 2634.95' south and township corner 2593.44' north, being the proportionate position. At the position for the corner, I placed a 1"x36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner, I found a squared wood post S30W, 64.0' with a Champion location poster facing it for an approximate corner. Removed the post and placed it adjacent to the monument.

(A3) Found and accepted monument as previously recorded at bearing and distance from the 1971 NBTs as follows: 12" Sugar N75E 40.1', 10" Sugar S09E 29.2'. Both trees have overgrown BH blazes. Scribing and notch visible on base blazes. Marked 2 new witnesses as described below. Found the original OT Sugar N81W at record bearing and distance, a rotted stump in poor condition with evidence of old blaze but notch and scribing not visible.

(10-Sec. 6) Found no evidence of prior monumentation or evidence of use at corner location. Established the corner midway and on a straight line between 1/4 corner 1317.48' north and section corner 1317.48' south. At the position for the corner, I placed a 1"x36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A2) Set 1" pipe with 4" aluminum cap. Blazed and scribed the following new bearing trees (bearings magnetic):
 22" Sugar N74W 10.9' "1/4S NBT"
 9" Sugar S21W 19.8' "1/4S NBT"
 8" Sugar S58E 34.4' "1/4S NBT"
 7" Sugar N59E 10.7' "1/4S NBT"

(A3) Found 1" pipe with 2" NPH brass cap. Blazed and scribed the following new bearing trees (bearings magnetic):
 12" Sugar N10W 42.9' "S1 NBT"
 16" Sugar S27N 35.3' "S12 NBT"

(10-Sec. 6) Set 1" pipe with 4" cap. Blazed and scribed the following bearing trees (bearings magnetic):
 9" Sugar N57E 14.1' "1/16S BT"
 8" Sugar S55E 17.1' "1/16S BT"
 9" Sugar S34W 35.0' "1/16S BT"
 9" Sugar N57N 22.6' "1/16S BT"
 Placed a 2" squared sugar post 1 ft. north of the corner.

Signed by Stephan J. Szyszkoski Date 6-28-93
 Surveyor's Michigan License No. 33986

