

(97)

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Iron

(County)	Located in:	Corner Code #
1. Public Land Survey	T 45N R 31W	03
	T 45N R 31W	01
	T 45N R 31W	03
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Stephan J. Szyszkoski, in a field survey on April 27, 1993, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(03) Quarter corner common to Sections 6-7. Corner previously recorded in 1971 by Arthur O. Enger, RLS as follows: 1" I.D. x 3/8" iron pipe with 4" aluminum cap placed at found cedar post set from original 0T. Witnesses to corner: Elm 8 N5 1/2W 22 links, N. Spruce 0 576 1/2E 54 1/2 links. Found no subsequent record.  
(01) Quarter corner common to Section 5 T45N-R31W and Section 32 T46N-R31W. Corner established in 1846 by U.S. Deputy Surveyor John Burt. Original 0Ts: Lynn 9 N34E 24, N. Pine 7 N35W 32. Found no subsequent record.  
(03) Quarter corner common to Sections 5-8. Corner established in 1849 by U.S. Deputy Surveyor John Burt. Original 0Ts: Sugar 12 N10W 30, Sugar 14 S68W 31. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**


(03) Found and accepted the corner monument as described above at record bearing and distance from the elm NBT, now dead. The N. Spruce NBT was not recovered. Marked 4 new bearing trees as described below.  
(01) Original post and accessories not recovered. Found 2 old N. Pine stumps in the corner area but neither show signs of having been marked. Found no acceptable evidence of the position of the original corner. Reestablished the corner on a straight line between section corners 2640.96' east and west, being the proportionate position. At the position for the corner, I placed a 1"x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.  
(03) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner. There was possibly a 1/2 error in the original measure on this line - it measures 0.68 ch. longer than record. Of 17 miles measured in this township during this survey, differences have typically ranged between -0.11 ch. and +0.13 ch. It was impossible to determine in which 1/2 mile the error was made and so the corner was reestablished on a straight line between section corners 2653.46' east and west, being the proportionate position. At the position for the corner, I placed a 1"x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(03) Found 1" pipe with 4" cap. Blazed and scribed the following new bearing trees (bearings magnetic): 5" Maple N50E 7.6' "1/4S NBT" 5" Maple S87E 9.5' "1/4S NBT" 14" Balsam S63W 34.1' "1/4S NBT" 5" Sugar N08W 24.5' "1/4S NBT" Set squared post adjacent to the corner.	(01) Set 1" pipe with 4" aluminum cap. Blazed and scribed the following new bearing trees (bearings magnetic): 12" Sugar N22E 13.4' "1/4S NBT" 7" Sugar S27E 9.4' "1/4S NBT" 10" Sugar S88W 3.5' "1/4S NBT" 6" Sugar N30W 17.3' "1/4S NBT" N35E 1.7', squared a 4" Sugar.	(03) Set 1" pipe with 4" aluminum cap. Blazed and scribed the following new bearing trees (bearings magnetic): 3" R. Pine N37W 37.2' "1/4S NBT" 2" R. Pine N14E 22.4' "1/4S NBT" 2" R. Pine N47E 25.2' "1/4S NBT" 4" Poplar West 32.2' "1/4S NBT" Corner falls on the division between a R. Pine plantation north (2-4" dia.) and a poplar regeneration south (1-2" dia.).
--	---	--

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986



Date 6-28-93