

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 45N R 31W	07
	T 45N R 31W	08
	T R	
	T R	
2. Property Controlling In Section	S 18 T 45N R 31W	14
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12							
5													
6	15	16	17	18	19	20	21	22	23	24			
7													
8	19	20	21	22	23	24							
9													
10	29	30	31	32	33	34	35	36					
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on June 09, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (07) Quarter corner common to Sections 17-20. Original corner established in 1849 by U.S. Deputy Surveyor John Burt. Original 8Ts: Cedar 10 N52W 11, Cedar 8 S43E 15. Found no subsequent record.
 (08) Quarter corner common to Sections 19-20. Original corner established in 1849 by U.S. Deputy Surveyor John Burt. Original 8Ts: Sugar 10 N68E 25, Fir 8 S75W 10. Found no subsequent record.
 (16-Sec. 18) East 1/16 corner between sections 18-19. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (07) Original post and accessories not recovered. The bearing trees have probably washed downstream long ago. The stream west of the corner has widened somewhat since the original survey. Found no acceptable evidence of the position of the original corner. Reestablished the corner midway and on a straight line between section corners 2636.18' east and west. At the position for the corner, I placed a 1"x36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. The water's edge of the fence River is 5' west of the corner.
 (08) Original corner and accessories not recovered. Corner falls in an old cut and burned over area. Found no acceptable evidence of the position of the original corner. Reestablished the corner midway and on a straight line between section corners 2640.46' north and south. Original ridge calls to north and south check well from this position. At the position for the corner, I placed a 1"x36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.
 (16-Sec. 18) Found no evidence of prior monumentation. Established the corner midway and on a straight line between 1/4 corner 1318.10' west and section corner 1318.10' east. At the position for the corner, placed a 1"x36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|---|--|---|
| (07) Set 1" pipe with 4" aluminum cap. Blazed and scribed the following new bearing trees (bearings magnetic):
26' W. Pine N04E 25.7' "1/4S NBT"
9' Spruce N38E 10.8' "1/4S NBT"
24' W. Pine S57E 28.2' "1/4S NBT"
24' W. Pine S82E 14.7' "1/4S NBT"
Placed a 3" squared spruce post adjacent to the corner. | (08) Set 1" pipe with 4" aluminum cap. Blazed and scribed the following new bearing trees (bearings magnetic):
3" Poplar S49W 4.2' "1/4S NBT"
4" Poplar S45E 8.6' "1/4S NBT"
5" Balsam N04W 54.8' "1/4S NBT"
4" Balsam N27W 37.3' "1/4S NBT" | (16-Sec. 18) Set 1" pipe with 4" cap. Blazed and scribed the following bearing trees (bearings magnetic):
3" Spruce S47W 22.9' "1/16S BT"
4" Balsam S08W 47.1' "1/16S BT"
3" Balsam S31E 21.1' "1/16S BT"
Set location poster on 2" poplar, West 1.9' |
|---|--|---|

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986



6-28-93