

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Town _____
County _____

Located In: _____ Corner Code # _____

1. Public Land Survey T 45W R 31N E3
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4													
5													
6	16	17	18	19	20	21	22	23	24	25	26	27	28
7													
8	18	19	20	21	22	23	24	25	26	27	28	29	30
9													
10	30	31	32	33	34	35	36	37	38	39	40	41	42
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, Stephan J. Szyszkoski, in a field survey on June 09, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E3) Corner common to Sections 4-5-8-9. Corner previously recorded in 1966 by Billy G. Buckler as follows: Set 1" pipe with 4" aluminum cap at old wood post in open Spruce marsh, with one original BT standing (Tamarack S84E 3.37 ch. Meas., tamarack 12 N25E 3.39 618). 1966 witnesses: 3" D. Spruce N34E 24.5 links, 2" tamarack N47W 43 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E3) Found and accepted corner monument as previously recorded at record bearing and distance from the 1966 witness trees, both in good condition with blazes overgrown. The original tamarack BT is still standing, a dead stub in excellent condition with scribing plain.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E3) Found 1" pipe with 4" cap.
Blazed and scribed the following new bearing trees (bearings magnetic):
3" Tamarack S70E 29.1' "89 NBT"
2" Tamarack N09W 15.1' "85 NBT"
3" Spruce S70W 18.1' "88 NBT"



Signed by Stephan J. Szyszkoski Date 6-28-93
Surveyor's Michigan License No. 33986