

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Iron

(County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 31W	E4
	T R	
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, Stephan J. Szyszkoski, in a field survey on January 19, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E4) Quarter corner common to Sections 8-9. Corner previously restored by single proportionate measurement to the original record in 1971 by Arthur O. Esger: Corner monument 1" I.D. x 36" iron pipe with 4" aluminum cap. NBTs: W. Spruce 3 N38W 43.0' 1/4S NBT, W. Spruce 5 N65E 50.5' 1/4S NBT. Bearings magnetic.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E4) Found 1" pipe with 4" aluminum MONR cap in good condition at record bearing and distance from the 1971 NBTs. Both trees are green but blazes have grown over. Scribing is not visible. Marked 3 new witness trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E4) Found 1" pipe with 4" MONR cap.

The 1971 witnesses:

9" W. Spruce N34W 43.0'

12" W. Spruce N65E 50.5'

Blazed and scribed the following new

bearing trees:

6" Maple N23W 24.0' 1/4S NBT

4" Maple N67W 24.9' 1/4S NBT

10" twin maple S24W 63.1' 1/4S NBT

North 12' E'ly gate post on road to a camp.

South 32' centerline of E-W road.

Signed by Stephan J. Szyszkoski

Date 2-3-94

Surveyor's Michigan License No. 33986

