

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Iron

(County)

Located In:

Corner Code #

1. Public Land Survey

T ___ R ___

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
 in Section

S 26 T 45N R 31W 5

S 26 T 45N R 31W 1

3. Miscellaneous
 Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Nov 01 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19___ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (5-Sec. 26) North 1/16 corner Section 26. Corner not established in the original survey. Found no subsequent record.
 (1-Sec. 26) West 1/16 corner between Sections 23-26. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(5-Sec. 26) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Quarter corner and Center of Section 1306.33' north and south. At the position for the corner, I placed a 1"IDx36' iron pipe capped with a 4" dia. cast aluminum MDHR tablet, appropriately stamped.
 (1-Sec. 26) Found the corner position monumented by a 1" square iron pin placed by unknown surveyor. I determined the monument to be 0.62' south of a straight line between Section corner to west and Quarter corner to east, and 0.08' east of the midpoint. I accepted the pin as a careful and faithful determination of the position of the corner. Left the pin in place and marked bearing trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(5-Sec. 26) Set 1" Pipe with 4" cap.	(1-Sec. 26) Found 1" square iron pin.
Blazed and scribed the following bearing trees:	Blazed and scribed the following bearing trees:
7" Spruce N54W 27.8' 1/16S BT"	12" Sugar S10E 12.7' 1/16S BT"
12" Ash N21E 23.8' 1/16S BT"	7" Sugar N27E 14.3' 1/16S BT"
7" Balsam S52E 12.0' 1/16S BT"	8" Sugar N37W 31.8' 1/16S BT"
9" Cedar S26W 45.4' 1/16S BT"	7" Sugar S34W 32.1' 1/16S BT"
Set a Squared cedar post adjacent.	Found a drill rod in a N-S fence line
Bearings are magnetic.	S41W 9.9'. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11-27-95

For the Michigan Department of Natural Resources - Forest Management Division