

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 45N R 31W	19
	T R	
	T R	
	T R	
2. Property Controlling In Section	S 26 T 45N R 31W	4
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Nov 01 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
(19) Corner common to Sections 22-23-26-27. Corner established in 1849 by John Burt: " 80.00 Set maple post corner of Sec. 22,23,26,27. Lynn 8 S28W 15, Meacock 10 N23E 28". Found no subsequent record.
(4-Sec. 26) Northwest 1/16 corner, Section 26. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(19) Original post and accessories not recovered. Found a 1" square iron pin adjacent to an old post with a 1 1/4" iron pipe, all at a fence corner with standing fence north and south. I note that the pin has been used in the past by at least two others as control for establishing 1/16 corners on the north and west lines of Section 26. I found distances east and south to re-monumented section corners to be 5285.01', and 5228.69', respectively. I accepted the pin as the best available evidence of the position of the original corner. Left the pin in place and marked 4 new witnesses as described below.

(4-Sec. 26) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners. At the position for the corner, I placed a 1" IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, I found a 1 1/2" iron pipe at a fence corner S05E 15.8' distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(19) Found 1" square iron pin.

Blazed and scribed the following new

bearing trees:

10" Sugar S37W 10.7' "S27 NBT"
10" Sugar N37W 17.6' "S22 NBT"
8" Sugar N25E 13.0' "S23 NBT"
7" Sugar S87E 4.8' "S26 NBT"

Bearings are magnetic.

(4-Sec. 26) Set 1" pipe with 4" cap.

Blazed and scribed the following bearing

trees:

7" Sugar S48E 10.8' "1/16S BT"
10" Sugar S89E 20.3' "1/16S BT"
12" Sugar N05W 38.4' "1/16S BT"
4" Sugar S88W 18.2' "1/16S BT"

Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11-27-95

For the Michigan Department of Natural Resources - Forest Management Division