

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located in:	Corner Code #
(County)		
1. Public Land Survey	T 45N R 31W	J9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Nov 01 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
(J9) Quarter corner common to Sections 23-26. Corner established in 1849 by John Burt: "West corrected between Sec. 23 & 26. 40.27 Set Cedar qr. sect. post. top of ridge 25 feet C SE. Cedar 14 N60E 11, Cedar 12 S20W 13. 41.50 Enter Swamp C SE. 48.10 Stream 1.25 C SE". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J9) Original post and accessories not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on a straight line between Section corners 2642.50' East and West. This position checks with the original record as to Ridge top, Enter Swamp, and Stream, noted above. The corner position falls in a 1 story wood-frame cabin on a concrete block foundation. I left the corner position unmonumented and established a WITNESS CORNER to the quarter corner 70.00' west of the 1/4 corner, on the Section line, a straight line between the 1/4 corner and the monumented west 1/16 corner between sections 23/26. At the position for the witness corner, I placed a 1"IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet appropriately stamped. In addition, I placed a REFERENCE CORNER to the 1/4 corner: a 1"IDx36" iron pipe capped with a yellow plastic cap stamped "MICH DNR 33986". The reference corner is northerly from the 1/4 corner 21.45' and is northeasterly from the witness corner 70.05'. The witness and reference corners form an angle with the 1/4 corner position of 81 deg. 19 min. 26 sec. See sketch on reverse side of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

WITNESS CORNER to J9: Set 1" iron pipe with 4" MDNR cap. Set nails with MDNR ref. tags in the following:
5" Balsam S12E 10.90'
4" Balsam N28E 1.70'
12" White Pine N41W 16.81'
12" Red Pine S52W 14.59'
East 51' West wall of cabin
NW corner of cabin N80E 50.1'
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11-27-95
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division