

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

IRON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. <u>X</u> , R. <u>31</u> W. <u>X</u>	J-7
2. PROPERTY CONTROLLING IN SECTION <u>14</u>	, T. <u>45</u> N. <u>X</u> , R. <u>31</u> W. <u>X</u>	15, 16
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner 15: Not set on original survey nor subsequently, apparently.
- Corner J-7: Original monument and accessories not found.
- Corner 16: Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner 15: Established 07-08-80 on line between corners east and west. Corner falls in middle of old road.
- Corner J-7: Reestablished 07-09-80 on line between corners east and west.
- Corner 16: Established 07-09-80 on line between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner 15: Set 1" I.D. x 30" iron pipe with 4" aluminum cap.
4" Aspen N80°W 51.0 ft., 1/16S, BT
3" Aspen S68°E 8.0 ft., 1/16S, BT
- Corner J-7: Set 1" I.D. x 32" iron pipe with 4" aluminum cap.
10" Spruce N78°E 34.4 ft., 1/4S, NBT
5" Spruce N29°W 30.4 ft., 1/4S, NBT
- Corner 16: Set 1" I.D. x 32" iron pipe with 4" aluminum cap.
7" W. Birch N55°W 16.1 ft., 1/16S, BT
7" Spruce S35°W 38.2 ft., 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl E. Johnson DATE 7-3-80


APPROVED AND SIGNED BY Keith L. Sackett DATE 7-3-80

MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006



FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET