

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	(IRON COUNTY) LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. R. <u>31</u> E. W.	South Meander Corner Between K-7 & K-9
2. PROPERTY CONTROLLING IN SECTION <u>23</u>	T. <u>45</u> N. R. <u>31</u> E. W.	14
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 10, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
South Meander Corner: Original monument and accessories not found.

Corner 14: Not set on original survey nor subsequently, apparently. Found fence corner for fence lines south and east N85°E - 12.9 ft.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
South Meander Corner: Restored on south shore of Hickman Lake on line between Section Corner 31.150 chains south and Section Corner 47.2745 chains north. 1/4 corner falls in lake.

Corner 14: Established on line between Section Corner 20.000 chains south and M.C. 11.150 chains north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
South Meander Corner: Set 1" I.D. x 32" iron pipe with 4" aluminum cap.
 3" Tamarack N85°W 28.9 ft., MC, NBT
 3" Tamarack S 8°E 14.3 ft., MC, NBT

Corner 14: Set 1" I.D. x 32" iron pipe with 4" aluminum cap.
 6" Aspen S76°E 14.4 ft., 1/16S, BT
 8" Aspen N44°W 54.0 ft., 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl E. Johnson DATE 9-3-80

APPROVED AND SIGNED BY Keith L. Sackett DATE 9-3-80

MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

