

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. 31 W.	#K-3 & K-4
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 25, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner K-3 (Section Corner 1, 2, 11, & 12, T45N, R31W):**
 Tamarack post (Not found. See B for subsequent monuments.)
 Tamarack 6 N75W 24 (Not found. No subsequent accessories found.)
 Tamarack 8 S40E 46 (Not found. No subsequent accessories found.)
- Corner K-4 (1/4 corner between Sections 11 & 12, T45N, R31W):**
 Y. Birch post (Not found. No subsequent monuments found.)
 Spruce 14 S87W 16 (Not found. No subsequent accessories found.)
 Sugar 8 N40E 22 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner K-3: Restored at a point S0°41.6'W 81.270 ch. from Sec. Cor. 1, 2, 35, & 36, 45, 46-31 and N0°20.4'E 239.478 ch. from Sec. Cor. 23, 24, 25, & 26, 45-31.**
 This appears to correspond with the original survey relationship, especially as to direction, as calls to lake and stream edges to S and stream to E agree very closely with the record. Found 2" x 2" squared wood posts N50°20'W (true) 11.9 ft. and S80°50'E (true) 45.6 ft. from corner and a 1-1/2" x 1-1/2" squared picked-post N79°E (mag.) 44.9 ft., indicating uncertainty by others as to the true corner location.
- Corner K-4: Restored on line between Section Corners 40.027 ch. to N and to S.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner K-3: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.**
 Jack Pine 11 N13°E (mag.) 81.8 ft. "S1, NBT"
 Tamarack 6 N79°W (mag.) 13.5 ft. "S2, NBT"
 Tamarack 7 S47°W (mag.) 12.2 ft. "S11, NBT"
 Declination 1°45' West.
- Corner K-4: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.**
 W. Pine 12 N42°E (mag.) 47.0 ft. "1/4S, NBT"
 W. Pine 6 S75°E (mag.) 71.8 ft. "1/4S, NBT"
 Declination 5°00' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 31, 1980

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger

Michigan Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 13581