

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>45</u> N. <u>X</u> , R. <u>31</u> <u>X</u> W.	<u>#K-5 &amp; L-5</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 24, 19 80, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner K-5 (Section Corner 11, 12, 13, & 14, T45N, R31W):**  
 Sugar post (Not found. No subsequent monuments found.)  
 Y. Birch 24 N15W 42 (Not found. No subsequent accessories found.)  
 Sugar 12 S35E 15 (Not found. No subsequent accessories found.)
- Corner L-5 (1/4 corner between Sections 12 & 13, T45N, R31W):**  
 Y. Birch post (Not found. No subsequent monuments found.)  
 Sugar 10 N22W 38 (Not found. No subsequent accessories found.)  
 Sugar 10 S 5E 15 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner K-5:** Restored on line between Sec. Cor. 23, 24, 25, & 26, 45-31 and Sec. Cor. 1, 2, 11, & 12, 45-31, 80.054 ch. S of the latter. There appears to have been a 1 chain error, in addition to a small index error, in the original survey measurement bet. this corner and a stream crossing (Michigan River) to S, thus the distances are not proportionate except for the index error. Distance to top of hill 24 ch. N of corner supports this restoration of the sec. corner.
- Corner L-5:** Restored on line between Sec. Corners 39.977 ch. to E and to W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner K-5:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Red Maple 5 N7-1/2°W (mag.) 24.4 ft. "S11, NBT"  
 Cherry 8 S89-1/2°W (mag.) 47.6 ft. "S14, NBT"  
 Declination 11°25' West.
- Corner L-5:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 W. Spruce 15 S23°W (mag.) 48.7 ft. "1/4S, NBT"  
 Cherry 12 S87°E (mag.) 15.2 ft. "1/4S, NBT"  
 Declination 0° 30' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson DATE March 31, 1980  
CHIEF OF SURVEY PART Carl R. Johnson

APPROVED AND SIGNED BY Arthur O. Enger DATE March 31, 1980  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

