

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(IRON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. R. 31 W.	#K-7 & L-7
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 26, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner K-7 (Section Corner 13, 14, 23, & 24, T45N, R31W):**  
 Spruce post (Not found. No subsequent monuments found.)  
 Cedar 12 S40E 20 (Not found. No subsequent accessories found.)  
 Fir 8 N45W 23 (Not found. No subsequent accessories found.)
- Corner L-7 (1/4 corner between Sections 13 & 24, T45N, R31W):**  
 Sugar post (Not found. No subsequent monuments found.)  
 Sugar 10 N10E 12 (Not found. No subsequent accessories found.)  
 Sugar 8 S45W 9 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner: Corner K-7:

Restored on line between Sec. Cor. 23, 24, 25, & 26, 45-31 and Sec. Cor. 1, 2, 11, & 12, 78.4245 ch N of the former. There appears to have been an error of about 1.58 ch. in the original survey measurement over Hickman Lake, thus the short distance and reason why proportion was not used. Distance bet. S edge of lake and Sec. Cor. S of it checks exactly; so does distance bet. N edge of lake and S edge of stream (Michigan River) N of it, therefore error must be in the measure over lake. Corner L-7: Restored on line bet. Sec. Cor. 40.014 ch. W and Sec. Cor. 39.014 ch. E. There appears to be a 1.00 ch. error in the original survey measurement of this sec. line, and specifically in the E 1/4-mile, as evidenced by the falling of prominent natural features mentioned in original record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner K-7:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 W. Spruce 18 N10°E (mag.) 48.1 ft. "S13, NBT"  
 B. Spruce 6 N86°W (mag.) 22.9 ft. "S14, NBT"  
 Declination 3°10' East.
- Corner L-7:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.  
 Red Maple 9 S60°W (mag.) 11.6 ft. "1/4S, NBT"  
 Red Maple 7 N2°E (mag.) 25.6 ft. "1/4S, NBT"  
 Also squared and scribed a Red Maple N60°E (mag.) 1.2 ft. from corner. Declination 2°40' East.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson DATE March 29, 1980  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY Arthur O. Enger DATE March 31, 1980  
MICHIGAN REGISTERED LAND SURVEYOR

**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

