

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(IRON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. <u>31</u> E. S. W.	<u>15</u>
2. PROPERTY CONTROLLING IN SECTION <u>11</u>	T. <u>45</u> N. <u>31</u> E. S. W.	<u>15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. S. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 12, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner 15:**
Original monument and accessories not found.
- Corner 15:**
Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner 15:**
Reestablished by proportion.
- Corner 15:**
Established on line midway between corners E & W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner 15:** Set 1" I.D. by 36" iron pipe with 3-1/2" aluminum cap.
8" Maple N84°E 29.2 ft., S11, NBT
6" Maple S51°W 34.5 ft., S15, NBT
- Corner 15:** Set 1" I.D. by 36" iron pipe with 3-1/2" aluminum cap.
6" Spruce N35°E 48.6 ft., 1/16S, BT
26" Red Pine S 8°W 73.7 ft., 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY Keith L. Sackett DATE 5/13/80
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

